

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 171-20592-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Spud 4/12/05

Well Operator: SunStone Operating Company, LLC KCC License #: 33802  
(Owner / Company Name) (Operator's)

Address: P. O. Box 35888 City: Tulsa

State: OK Zip Code: 74135 Contact Phone: ( 918 ) 621 - 6533

Lease: Schmidt Trust Well #: 10-1 Sec. 10 Twp. 19 S. R. 31  East  West

- NW - NE - NW Spot Location / QQQQ County: Scott

330 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1840 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 10-3/4" Set at: 330' Cemented with: 270 Sacks

Production Casing Size: 7-5/8" Set at: 4393' Cemented with: 720 Sacks

List (ALL) Perforations and Bridgeplug Sets: \_\_\_\_\_

Elevation: 2937 ( G.L. /  K.B.) T.D.: 4400' PBTD: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Separate page attached.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Billie Griggs Phone: ( 405 ) 601 - 1538

Address: 101 N. Robinson, Suite 810 City / State: Oklahoma City, OK

Plugging Contractor: Cheyenne Well Service KCC License #: KLN 6454  
(Company Name) (Contractor's)

Address: P. O. Box 384, Ness City, KS 67560 Phone: ( 800 ) 886 - 2207

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 12/4/06 Authorized Operator / Agent: C Swan Connie Swan  
(Signature) **KCC WICHITA**

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 15 2006

Attachment to CP-1 Well Plugging Application  
Schmidt Trust 10-1  
API 15-171-20592-0000

- 1.) Run tubing to shoe @ 4393', mix and pump 20 sacks of fresh water gel, 400# cotton seed hulls and 50 sacks of cement. (mix some hulls w/cement).
- 2.) Pull tubing to 3100', mix and pump 50 sacks cement.
- 3.) Pull tubing to 1700', mix and pump 75 sacks of cement.
- 4.) Pull tubing to 1000', mix and pump 50 sacks of cement.
- 5.) Pull tubing to 350', mix and pump 50 sacks of cement.
- 6.) Pull tubing to 60', circ. cement to surface.
- 7.) Pressure test 7 5/8 X 10 3/4 annulus to 500 psi. Have at least 50 sacks of cement to pump.

RECEIVED  
DEC 15 2006  
KCC WICHITA

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Sunstone Operating Company, LLC  
101 N. Robinson, Suite 810  
Oklahoma City, OK 73102

December 19, 2006

Re: SCHMIDT TRUST #10-1  
API 15-171-20592-00-00  
NWNENW 10-19S-31W, 330 FNL 1840 FWL  
SCOTT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



Barry Metz  
Deputy Director

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888