

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-207-01973-00-00

API # 15-Not Known (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Early 1970's ??? UNKNOWN

Well Operator: Cross Oil LLC (Owner / Company Name) KCC License #: 32044 (Operator's)

Address: PO Box 94 City: Hamilton

State: KS Zip Code: 66853 Contact Phone: (620) 678 - 3813 (620)437-6219

Lease: Wolfe Well #: 1 Sec. 4 Twp. 24 S. R. 14 East West
Kcc with/open

NE 1/4 Spot Location / QQQQ County: Woodson

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: unknown Cemented with: unknown Sacks

Production Casing Size: 4 1/2" Set at: 1688' Cemented with: Top of cement approx 1250' Sacks

List (ALL) Perforations and Bridgeplug Sets: 8 Shots 1672' to 1677'

Elevation: G.L. / K.B. T.D.: 1688 PBTD: _____ Anhydrite Depth: 1672 to 1677
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Tubing and packer hung in hole, run 1" to 1625' and pump 20 scks cement. Then shoot tubing off above packer and pull out, take out approx 700' 4 1/2" casing, run tubing in and pump in enough cement for 50' bridge or more, pull tubing to surface specifications and pump cement to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? ACO-1 is with this form

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dennis Smith & Brian Maclaskey

Phone: (620) 437 - 6219 620-437-6650

Address: PO Box 94 City / State: Hamilton, KS

Plugging Contractor: Consolidated Oil Well Service KCC License #: 31440
(Company Name) *(Contractor's)*

Address: PO Box 103 Phone: (620) 583 - 7664

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-28-06 Authorized Operator / Agent: Dennis Smith
lln 8006 *(Signature)*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 13 2006
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Cross Oil, L.L.C.
101 S. 5th St.
PO Box 94
Hamilton, KS 66853

December 11, 2006

Re: Wolfe #1
API 15-207-01973-00-00
NENENE 4-24S-14E, 330 FNL 330 FEL
WOODSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300

Sincerely



Barry Metz
Deputy Director