

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-001-02198-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date December 1958.

Well Operator: L & G Petroleum Operating LLC KCC License #: 32851
(Owner / Company Name) (Operator's)
Address: 1396 South Dakota Rd (1000 Camino del Oeste) City: Iola (Bakersfield)
State: Kansas (CA-93309) Zip Code: 66749 Contact Phone: (620) 365 - 7435

Lease: Bowlus A Well #: 9N Sec. 15 Twp. 24S S. R. 18 East West
NW NW - SW - W2 - SE4 Spot Location / QQQQ County: Allen

1265 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2600 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8.25 Set at: 15 ft Cemented with: _____ Sacks

Production Casing Size: 2.375 Set at: 895 Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: 6.25" Clayton packer set at 867 ft. with 20 sacks cement run on packer according to driller report
(copy included)

Elevation: _____ (G.L. / K.B.) T.D.: 893 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Run 1 inch pipe to 875 ft. / cement to surface

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? unknown if ACO-1 is on file or not

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Randy Stanley

Phone: (620) 365 - 7435

Address: 1396 South Dakota Rd City / State: Iola, KS

Plugging Contractor: Consolidated Oil Well Services KCC License #: 31440
(Company Name) (Contractor's)

Address: Chanute, KS Phone: (620) 431 - 9210

Proposed Date and Hour of Plugging (if known?): Before Dec 31, 2006

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: Dec 7-06 Authorized Operator / Agent: Randy Peterson
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 11 2006
KCC WICHITA

Boxius Farm
Well No. 12 M-10-A

State of Kansas
Allen County
Section 15-24-18
Southwest Quarter Southwest Quarter
25' from west line of quarter section
1265' from south line of quarter section
Commenced Spudding December 5, 1958
Finished Drilling December 13, 1958

J-11
J-11
240' in hole
9-N-15

| Thickness of Strata | Formation | Total Depth | Remarks |
|---------------------|-------------|-------------|---|
| 3 | Soil | 3 | Drive Pipe set 15' |
| 4 | Clay | 7 | |
| 6 | Gravel | 13 | Water |
| 37 | lime | 50 | |
| 27 | Shale | 77 | |
| 8 | lime | 85 | |
| 38 | Shale | 123 | |
| 70 | lime | 193 | |
| 4 | Blk Shale | 197 | Water |
| 54 | lime | 251 | |
| 15 | Shale | 266 | |
| 49 | Sand | 315 | Gas |
| 107 | Shale | 422 | |
| 5 | lime | 427 | |
| 8 | lime Shells | 435 | |
| 20 | lime | 455 | 30' |
| 10 | Shale | 465 | |
| 25 | Sand | 490 | |
| 28 | Shale | 518 | |
| 37 | lime | 555 | 40' |
| 16 | Blk Shale | 571 | |
| 23 | lime | 594 | 20' |
| 11 | Blk Shale | 605 | |
| 4 | lime | 609 | 5' - 617' correct |
| 229 | Shale | 838 | 7" cased @ 621' |
| 12 | Gas Sand | 850 | little gas |
| 8 | Oil-Sand | 858 | Gas - S.L.M. run @ 858' (50,000 cuft.) |
| 5 1/2 | Oil-Sand | 863 1/2 | Show - Hole correct |
| 5 1/2 | Oil-Sand | 869 | Show |
| 6 | Oil-Sand | 875 | Show |
| 4 1/2 | Oil-Sand | 879 1/2 | Oil-Showing |
| 6 1/2 | Oil-Sand | 885 1/2 | Good-Showing |
| 3 1/2 | Oil-Sand | 889 1/2 | Good-Showing |
| 4 | Oil-Sand | 893 1/2 | Showing |
| | Total Depth | 893 1/2 | Shale on bottom of bit - 6 gallon oil every 30 minutes. |

1-6 1/2" Clayton Packer set @ 857 1/2'
1-2" Seating Nipple set @ 885 1/2'
20 Sacks cement run on packer

-Material Used in Hole-
6 1/2" Drive Pipe 15'
2" Tubing 895'
1" Tubing 890'
1-6 1/2" Clayton Packer
1-2" Seating Nipple
1-2" Casing
1-2" Perforation
1-2" Working Barrel

RECEIVED
DEC 11 2006
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

L & G PETROLEUM COMPANY
1396 SOUTH DAKOTA RD.
IOLA, KANSAS 66749

December 19, 2006

Re: BOWLUS A #9N
API 15-001-02198-00-00
NWNWSWSE 15-24S-18E, 1265 FSL 2600 FEL
ALLEN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300

Sincerely



Barry Metz
Deputy Director