

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: McPherson Drilling Co.

Address: 15256 112th Road, Winfield, KS 67156

Phone: (620) 221-3560 Operator License #: 5495

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/24/2006 (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 2980 Bottom: T.D. 3048

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15 - 035-20,949 -00-00

Lease Name: Drake

Well Number: #3

Spot Location (QQQQ): SW - SE - NE -

2993 Feet from North / South Section Line

996 Feet from East / West Section Line

Sec. 13 Twp. 31S S. R. 5 East West

County: Cowley

Date Well Completed: 3/19/1976

Plugging Commenced: 8/21/2006

Plugging Completed: 8/24/2006

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Mississippi, 2980, 8 5/8", 170', None. Row 2: 4 1/2", 3043', 1209'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Graveled to 2865', set 6 sax cement. Shot at 1508, 1334 and 1209', pulled 1209' of 4 1/2" casing and laid pipe down.

Cemented from 250' to surface - United Cementing.

Name of Plugging Contractor: McPherson Drilling Co. License #: 5495

Address: 15256 112th Road, Winfield, KS 67156

Name of Party Responsible for Plugging Fees: McPherson Drilling Co.

State of Kansas County, Cowley, ss.


(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Penny McPherson

(Address) 15256 112th Road, Winfield, KS 67156

SUBSCRIBED and SWORN TO before me this 29th day of November, 2006

Carol A. Charters My Commission Expires: 08-01-2009 Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED DEC 11 2006 KCC WICHITA

Handwritten initials/signature