

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Exxon Mobil Oil Corporation  
Address: PO Box 4358 Houston TX 77210  
Phone: (281) 364 5073 Operator License #: 5208  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 9-18-06 (Date)  
by: Eric MacLaren (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chester Depth to Top: 5490 Bottom: 5505 T.D. 5587  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-081-20001-00-00  
Lease Name: Wayne Lucas  
Well Number: 3 <sup>receipt due per BDNs</sup>  
Spot Location (QQQQ): NE-SE-NE  
1830 Feet from  North /  South Section Line  
610 Feet from  East /  West Section Line  
Sec. 21 Twp. 28 S. R. 34  East  West  
County: Haskell  
Date Well Completed: 2-12-67  
Plugging Commenced: 9-18-06  
Plugging Completed: 9-20-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	788'	8 5/8	788	—
production		0	5586'	4 1/2	5586	850

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8 to 2850 (DV tool @ 2903) Circ. hole w/mud & mixed 200 lb. hulls & 20 sx cmt plug from 2850 to 2650. (Fish in 4 1/2 - top @ 4860) Cut & pull 4 1/2 to 820. Circ hole w/mud. 50 sx 820 to 670 tag @ 696 30 sx 400-300 10 sx 40-0 Capped 8 5/8 3 ft below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9737  
Name of Party Responsible for Plugging Fees: EXXON MOBIL PROD CO  
State of KANSAS County, STEVENS, ss. \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 18 2006  
CONSERVATION DIVISION  
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC, State of Kansas  
DORETTA L. DELAY  
My Appt. Exp. 12-27-08

(Signature) RB Jewer  
(Address) 200 W 4TH HUGOTON KS 67951

SUBSCRIBED and SWORN TO before me this 16 day of November, 2006  
Doretta L. Delay My Commission Expires: 12-27-08  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

regulatory contact: Jacqueline Davis 12/15/06 281-654-1913 AKT