

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Carmen Schmitt Inc.
Address: PO Box 47
Phone: (620) 793-5100 Operator License #: 6569
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/11/06 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 4019 Bottom: 4036 T.D. 4036
Lansing / KC Depth to Top: 3997 Bottom: 4012 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-01256-00-00
Lease Name: Ogallah Unit KCC Per 12/20/06
Well Number: 4-5 per A-1
Spot Location (QQQQ): _____ - SW - NE - SW
1650 Feet from North / South Section Line
3630 Feet from East / West Section Line
Sec. 26 Twp. 12 S. R. 22s East West
County: Trego
Date Well Completed: July, 1952
Plugging Commenced: 12/11/06
Plugging Completed: 12/11/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	304	8 5/8"	304'	0
		0	4019	5 1/2"	4019'	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU DS&W Well Service, Ran 2 3/8" tubing to 3575'. Rigged up Allied Cementing and Heartland Tank Service to plug well. Hooked up to surface pipe and mixed 100 sacks cement and 100 lbs of hulls. Hooked up to tubing and pumped 100 sacks of cement and 300# hulls. Pulled tubing to 2500 and mixed another 100 sacks of cement. Cement circulated to surface. Pulled rest of tubing out and filled casing with 25 more sacks of cement. Case Morris of KCC on hand to witness.

Name of Plugging Contractor: DS&W Well Servicing, Inc. License #: 6901
Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.
State of Kansas County, Barton, ss.

Jacob L. Porter (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L. Porter
(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 14th day of December, 20 06
Elaine Schreck My Commission Expires: 12-13-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 15 2006
KCC WICHITA