

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Carmen Schmitt Inc.
 Address: PO Box 47
 Phone: (620) 793-5100 Operator License #: 6569
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 12/11/06 (Date)
 by: Case Morris (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 4004 Bottom: 4034 T.D. 4034
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-32677-00-00
 Lease Name: Ogallah Unit KCC Per CP-1 PKT
5-2 12/20/06
 Well Number: _____
 Spot Location (QQQQ): _____ - nw - ne - se
2310 Feet from North / South Section Line
990 Feet from East / West Section Line
 Sec. 26 Twp. 12 S. R. 22s East West
 County: Trego
 Date Well Completed: April 1964
 Plugging Commenced: 12/11/06
 Plugging Completed: 12/11/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	325	8 5/8"	325	0
		0	4004	5 1/2"	4004	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU DS&W Well Service. Ran 2 3/8" tubing to 2940'. Rigged up Allied Cementing and Heartland Tank Service to plug well. Mixed 100 sks 60/40 poz, 10% gel, and 400# hulls. Pulled tubing to 1500' and mixed 150 sks cement and 400# hulls. Circulated cement to surface. Pulled tubing out of hole and put 5 1/2" swedge on casing, Pumped 20 sks down casing and shut in. Hooked up on surface pipe and mixed 50 sks of cement and 100# hulls. Pressured up to 200 psi and shut in. Case Morris with KCC on hand to witness.

Name of Plugging Contractor: DS&W Well Servicing, Inc. License #: 6901
 Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.
 State of Kansas County, Barton, ss.

Jacob L. Porter (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L. Porter
 (Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 14th day of December, 20 06

Elaine Schreck My Commission Expires: 12-13-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 15 2006
KCC WICHITA