

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-23,245-00-00

LEASE NAME McCall

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2-36

2,010 Ft. from N Section Line

1,340 Ft. from E Section Line

SEC. 36 TWP. 10S RGE. 23 W or (W)

COUNTY Graham

Date Well Completed 11-24-06

Plugging Commenced 11-24-06

Plugging Completed 11-24-06

LEASE OPERATOR RUSSELL OIL, INC.

ADDRESS PO Box 1469, Plainfield, IL 60544

PHONE#(815) 609-7000 OPERATORS LICENSE NO. 3293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-24-06 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3,775'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	219'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Push plug to 1,775', pump 25 sax cement on plug thru drill pipe; push plug to 1,000', pump 100 sax cement on plug thru drill pipe; push plug to 275', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RUSSELL OIL, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Burton Beery, Drilling Supt.

Contractor

(Employee of Operator or Contractor)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith, the same are true and correct, so help me God.

(Signature) Burton Beery

(Address) PO Box 709, Russell, KS 67665

RECEIVED

DEC 14 2006

SUBSCRIBED AND SWORN TO before me this 11th day of December, 2006

KCC WICHITA

My Commission Expires:



Ruth Phillips  
Notary Public