

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10093-00-00
Spot: W2E2SW Sec/Twnshp/Rge: 25-27S-11W
1343 feet from S Section Line, 3730 feet from E Section Line
Lease Name: CUNNINGHAM UNIT B Well #: 36
County: PRATT Total Vertical Depth: 3488 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC. DBA CRYSTAL R
Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		635		WITH 5 SX CMT
CIBP		3233		WITH 5 SX CMT
PROD	5.5	3488	0	WITH 175 SX CMT
SURF	8.625	372		WITH 200 SX CMT

\$ 113.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2006 12:30 PM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: DON CAMPBELL Company: KC RESOURCES Phone: (970) 920-0245

Proposed Plugging Method: CIBP @ 3400' WITH 5 SX CMT. PUMP 300-400 HULLS AND 25 SX CMT. PERFORATE AT 630' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2006 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3233' & 5 SX CMT WITH DUMP BAILER. SET CIBP @ 635' PLACED 5 SX CMT ON TOP OF PLUG WITH DUMP BAILER. PUMPED 190 SX CMT DOWN 5 1/2" CASING. CIRCULATED CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS. COULDN'T PRESSURE CMT UP DUE TO BAD BRADEN HEAD.

Perfs:

Top	Bot	Thru	Comments
3427	3488	OH	

INVOICED
DATE 12-18-06
INV. NO. 2007061007

Remarks: USED 60/40 POZMIX 4% GEL BY UNITED CEMENTING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey

(TECHNICIAN) RECEIVED

DEC 14 2006

KCC WICHITA

[Handwritten signature]
[Handwritten initials]