

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23390-00-00
Spot: SENENE Sec/Twnshp/Rge: 7-14S-14W
900 feet from N Section Line, 330 feet from E Section Line
Lease Name: MAAB A Well #: 1
County: RUSSELL Total Vertical Depth: 3400 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	495		

\$ 110.50

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/14/2006 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 145 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 11/14/2006 1:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3275' w/25 sxs.
2nd. Plug at 950' w/25 sxs.
3rd. Plug at 550' w/60 sxs.
4th. Plug at 40 w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 12-20-06
INV. NO. 2007061016

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

[Handwritten Signature]
(TECHNICIAN)

RECEIVED

DEC 18 2006

KCC WICHITA

Form CP-2/3

DEC 12 2006

[Handwritten Initials]