

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

CONFIDENTIAL

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 32916
Name: Premiere Corporation
Address: P O BOX 529
City/State/Zip: Wellington KS 67152
Purchaser: _____
Operator Contact Person: W. C. Long, JR
Phone: (620) 326-7471
Contractor: Name: Berentz Drilling Company, Inc.
License: 5892
Wellsite Geologist: Bob Pfannenstiel

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 15 2004

CONSERVATION DIVISION
WICHITA, KS

KCC

MAR 18 2004

Designate Type of Completion:
 New Well _____ Re-Entry _____ Workover _____
 Oil _____ SWD SLOW _____ Temp. Abd.
_____ Gas _____ ENHR _____ SIGW
_____ Dry _____ Other (Core, WSW, Expl., Cathodic, etc)

CONFIDENTIAL

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
_____ Deepening _____ Re-perf. _____ Conv. to Enhr./SWD
_____ Plug Back _____ Plug Back Total Depth
_____ Commingled _____ Docket No. _____
_____ Dual Completion _____ Docket No. _____
_____ Other (SWD or Enhr.?) _____ Docket No. _____

11-18-03 11-30-03
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 077-21467-00-00
County: Harper
_____ NE _____ SE _____ NW Sec. 25 Twp. 31 S. R. 6 East West
3630 feet from (S) N (circle one) Line of Section
2970 feet from (E) W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE (SE) NW SW
Lease Name: Long Well #: 1
Field Name: Runnymede

Producing Formation: Kansas City Lime
Elevation: Ground: 1375 Kelly Bushing: 1380
Total Depth: 4699 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 228 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.
Act I W/HR 12-8-06

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 26000 ppm Fluid volume 800 bbls
Dewatering method used Fluids hauled and then evaporation
Location of fluid disposal if hauled offsite:
Operator Name: Bear Petroleum, Inc.
Lease Name: Graber SWD License No.: 4419
Quarter _____ Sec. 4 Twp. 27 S. R. 6 East West
County: Kingman Docket No.: D98310, C22284

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Karen Amrein
Title: CONSULTANT Date: 3/15/04
Subscribed and sworn to before me this 15th day of March,
2004.
Notary Public: Karen Amrein
Date Commission Expires: _____

KAREN AMREIN
Notary Public - State of Kansas
My Appt. Expires April 13, 2004

KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
_____ Wireline Log Received
_____ Geologist Report Received
_____ UIC Distribution

CONFIDENTIAL

Side Two

KCC
MAR 18 2004

ORIGINAL

Operator Name: Premiere Corporation Lease Name: Long Well #: 1
Sec. 25 Twp. 31 S. R. 6 East West County: Harper

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Kansas City Lime	3605	-2225
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Marmaton Lime	3836	-2456
List All E. Logs Run:	Compensated Neutron Log	Mississippi	4199	-2819
	Compact Photo-Density Log	Kinderhook Shale	4529	-3149
	Micro-Resisitivity Log	Simpson	4629	-3249

Array Induction Log

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	23	237	60/40 Poz	165	3% CC
Production	7 7/8	5 1/2	15.50	4699	Type H	235	10% Salt

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2004
CONSERVATION DIVISION
WICHITA, KS

PERFORATION RECORD - Bridge Plugs Set/Type
Specify Footage of Each Interval Perforated

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
3	KC Lime 3748-55	750 gal 15% HCL	3748

TUBING RECORD

Size 2-3/8" Set At 3800 Packer At _____ Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. _____ Producing Method Flowing Pumping Gas Lift Other (Explain) _____

Estimated Production Per 24 Hours	Oil Bbbs.	Gas Mcf	Water Bbbs.	Gas-Oil Ratio	Gravity

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled _____

Production Interval Other (Specify) _____

Allied Cementing Co., Inc
P.O. Box 31
Russell, KS 67665

CONFIDENTIAL

*** STATEMENT ***

ORIGINAL

STATEMENT DATE: 12/17/03

CUSTOMER ID.: Frem

RECEIVED
KANSAS CORPORATION COMMISSION

PAGE: 1

MAR 15 2004

CONSERVATION DIVISION
WICHITA, KS

KCC
MAR 18 2004

CONFIDENTIAL

=====
Premiere Corporation
P. O. Box 529
201 W. Harvey
Wellington, KS 67152-0529
=====

Payable 30 days following date of invoice. 1 1/2% Charged Thereafter.

INVOICE	DATE	TERMS OR REF	CODE	DEBITS	CREDITS	CUMULATIVE BALANCE
091645	11/26/03	Invoicing	SA	2469.09		2469.09
091741	11/30/03	Invoicing	SA	9354.96		11824.05
				11824.05	0.00	11824.05

CURRENT	1 - 30 PAST DUE	31 - 60 PAST DUE
11824.05	0.00	0.00
OVER 60 PAST DUE	OPEN CR	TOTAL
0.00	0.00	11824.05

=====
TOTAL DUE 11824.05
=====

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# [REDACTED]

CONFIDENTIAL

ORIGINAL

 * I N V O I C E *

Invoice Number: 091645

Invoice Date: 11/26/03

KCC

MAR 18 2004

RECEIVED
 KANSAS CORPORATION COMMISSION

MAR 15 2004

CONFIDENTIAL

CONSERVATION DIVISION
 WICHITA, KS

Sold Premiere Corporation
 To: P. O. Box 529
 201 W. Harvey
 Wellington, KS
 67152-0529

Cust I.D.....: Prem
 P.O. Number...: W. C. Long #1
 P.O. Date.....: 11/26/03

Due Date.: 12/26/03
 Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	99.00	SKS	7.1500	707.85	T
Pozmix	66.00	SKS	3.8000	250.80	T
Gel	3.00	SKS	10.0000	30.00	T
Chloride	5.00	SKS	30.0000	150.00	T
Handling	173.00	SKS	1.1500	198.95	E
Mileage (40)	40.00	MILE	8.6500	346.00	E
173 sks @\$.05 per sk per mi					
Surface	1.00	JOB	520.0000	520.00	E
Mileage pmp trk	40.00	MILE	3.5000	140.00	E
Wood plug	1.00	EACH	45.0000	45.00	T

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ **238.86**
 ONLY if paid within 30 days from Invoice Date

Subtotal: 2388.60
 Tax.....: 80.49
 Payments: 0.00
 Total....: 2469.09

*Pd 12-19-03
 CK
 1008*

ALLIED CEMENTING CO., INC.

CONFIDENTIAL

P.O. BOX 31
RUSSELL, KANSAS 67665

KCC

MAR 18 2004

14082
ORIGINAL

SERVICE POINT:

Med. Lodge, KS

DATE 11-19-03	SEC. 25	TWP. 31s	RANGE low	ON LOCATION 9:00 AM	JOB START 9:30 AM	JOB FINISH 10:00 AM
LEASE W.C. Long	WELL # 1	LOCATION Harper #2 Jct, 4 mi to			COUNTY Harper	STATE KS
OLD OR <u>NEW</u> (circle one)		Chicago Baptist Church 2 1/4 E, 1/4 S, E into				

CONTRACTOR Berentz OWNER Premier Corp.

TYPE OF JOB Surface

HOLE SIZE 12 1/4" T.D. 238' CEMENT AMOUNT ORDERED 165 sx 60:40:2+3%cc

CASING SIZE 8 5/8 24.20 DEPTH 227.70

TUBING SIZE DEPTH

DRILL PIPE 4 1/2" DEPTH 238

TOOL DEPTH

PRES. MAX MINIMUM 50

MEAS. LINE SHOE JOINT 15'

CEMENT LEFT IN CSG. 15'

PERFS.

DISPLACEMENT 14 bbl fresh h₂O

EQUIPMENT

PUMP TRUCK CEMENTER Mike Rucker HELPER Eric Brewer

BULK TRUCK # 240 DRIVER Thad Cantrall

BULK TRUCK # DRIVER

REMARKS:

9:30 AM pipe on bottom break circ. with truck took

2 bbl. 9:40 AM Start Cement: 165 sx 60:40:2+3%cc

@ 14.8 mi light 9:45 AM Stop Pumps Release Plug, Start

Disp. 300# @ 9:55 AM Pump 14 bbl fresh h₂O, shut-in

Cement Did Circulate!

Circ. 50s x to pit.

CHARGE TO: Premier Corp.

STREET

CITY STATE ZIP

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment

and furnish cementer and helper to assist owner or

contractor to do work as is listed. The above work was

done to satisfaction and supervision of owner agent or

contractor. I have read & understand the "TERMS AND

CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX

TOTAL CHARGE [scribble]

DISCOUNT [scribble] IF PAID IN 30 DAYS

PRINTED NAME A. Rush

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TOTAL 1683.60

TOTAL 705.00

FLOAT EQUIPMENT NONE

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566

KCC

MAR 18 2004

ORIGINAL

 * INVOICE *

CONFIDENTIAL

CONFIDENTIAL

Invoice Number: 091741

Invoice Date: 11/30/03

RECEIVED
 KANSAS CORPORATION COMMISSION

MAR 15 2004

CONSERVATION DIVISION
 WICHITA, KS

Sold Premiere Corporation
 To: P.O. Box 529
 201 W. Harvey
 Wellington, KS
 67152-0529

Cust I.D.....: Prem
 P.O. Number...: Long #1
 P.O. Date.....: 11/30/03

Due Date.: 12/30/03
 Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common "H"	250.00	SKS	8.7000	2175.00	T
Salt	27.00	SKS	7.5000	202.50	T
GypSeal	24.00	SKS	17.8500	428.40	T
KolSeal	1500.00	LBS	0.5000	750.00	T
ClaPro	12.00	GAL	22.9000	274.80	T
FL-160	188.00	LBS	8.0000	1504.00	T
Handling	336.00	SKS	1.1500	386.40	E
Mileage (40)	40.00	MILE	16.8000	672.00	E
336 sks @\$.05 per sk per mi					
Production	1.00	JOB	1264.0000	1264.00	E
Mileage pmp trk	40.00	MILE	3.5000	140.00	E
Float Shoe	1.00	EACH	263.0000	263.00	T
Latch Down Plug	1.00	EACH	350.0000	350.00	T
Centralizers	5.00	EACH	50.0000	250.00	T
Baskets	2.00	EACH	128.0000	256.00	T

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ **891.61**
 ONLY if paid within 30 days from Invoice Date

Subtotal:	8916.10
Tax.....:	438.86
Payments:	0.00
Total....:	9354.96

*Pal 12-19-03
 CLK 1009*

CONFIDENTIAL

ALLIED CEMENTING CO., INC

KCC

ORIGINAL 14065

TO P.O. BOX 31
RUSSELL, KANSAS 67665

MAR 18 2004

SERVICE POINT
Mid Lodge

DATE <u>1/29-03</u>	SEC <u>25</u>	TWP <u>31S</u>	RANGE <u>6W</u>	CONFIDENTIAL SIZED OUT	ON LOCATION <u>7:00 AM</u>	JOB START <u>4:15 AM</u>	JOB FINISH <u>5:00 AM</u>
LEASE <u>Long</u>	WELL # <u>1</u>	LOCATION <u>Harper 10D+2 Jct</u>		COUNTY <u>Harper</u>	STATE <u>Ks</u>		
OLD OR NEW (Circle one) <u>NEW</u>				<u>4 N/E 2 1/4 E 1/4 S E</u>			

CONTRACTOR <u>A Perentz</u>	OWNER <u>Premiere Corp</u>
TYPE OF JOB <u>Production</u>	
HOLE SIZE <u>7 7/8</u>	T.D. <u>4699</u>
CASING SIZE <u>5 1/2 x 15.5</u>	DEPTH <u>4695</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>latch down Baffle</u>	DEPTH <u>4675</u>
PRES. MAX <u>1800</u>	MINIMUM
MEAS. LINE	SHOE JOINT <u>20</u>

CEMENT LEFT IN CSG.	CEMENT	AMOUNT ORDERED	<u>250 5x Class 4, 10% salt</u>
PERFS.	10% Gyp-Seal (#kol-seal +, 1890, FI-KO		<u>(use 15 sx rat)</u>
DISPLACEMENT <u>105 BBLs 2% KCl water</u>	COMMON <u>H 250</u>	@ <u>8.70</u>	<u>2175.00</u>
EQUIPMENT	POZMIX	@	
	GEL <u>salt 27</u>	@ <u>7.50</u>	<u>202.50</u>
	CHLORIDE	@	
	Gyp-Seal <u>24</u>	@ <u>17.85</u>	<u>428.40</u>
	Kol-seal <u>1500#</u>	@ <u>.50</u>	<u>750.00</u>
	FI-KO <u>188#</u>	@ <u>8.00</u>	<u>1504.00</u>
	Clapro <u>12 gals</u>	@ <u>22.90</u>	<u>274.80</u>
	HANDLING <u>336</u>	@ <u>1.15</u>	<u>386.40</u>
	MILEAGE <u>336 x 40</u>	@ <u>.05</u>	<u>672.00</u>
	RECEIVED		
	KANSAS CORPORATION COMMISSION		
			TOTAL <u>6393.10</u>

PUMP TRUCK # <u>372</u>	CEMENTER <u>Justin Hart</u>
BULK TRUCK # <u>353-314</u>	HELPER <u>Mark Brungardt</u>
BULK TRUCK #	DRIVER <u>Larry Goldsberry</u>
BULK TRUCK #	DRIVER

MAR 15 2004

REMARKS:
Pipe on BTM. Break Circ
3 BBLs Fresh #3
Plug Rat 15 sx # + Additive @ 14.8
235 sx # + Additives @ 14.8
Release Plug Diss 105 BBLs 2%
Kcl Water 1000 Plug 900-1800
Release PSI Float Held

CONSERVATION DIVISION WICHITA, KS	SERVICE
DEPTH OF JOB <u>4699</u>	
PUMP TRUCK CHARGE	<u>264.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>40</u>	@ <u>3.50</u> <u>140.00</u>
PLUG	@
	@
	@
	@
	TOTAL <u>1404.00</u>

CHARGE TO: Premiere Corp
STREET P.O. Box 529
CITY WELLINGTON STATE KS ZIP 67152 562

FLOAT EQUIPMENT	
Floaty Shoe	@ <u>263.00</u>
latch down Plug	@ <u>350.00</u>
3 Centralizers	@ <u>50.00</u> <u>250.00</u>
2 Baskets	@ <u>28.00</u> <u>256.00</u>
	@
	TOTAL <u>1219.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE ~~6393.10~~
DISCOUNT ~~6393.10~~ IF PAID IN 30 DAYS

SIGNATURE Robert F. Pfannenstiel Robert F. Pfannenstiel
PRINTED NAME

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING