

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

RECEIVED  
KCC DISTRICT #2  
NOV - 6 2006  
WICHITA, KS

15-053-00786-00-01  
15-053-00786-00-01

WELL PLUGGING APPLICATION FORM

PLEASE TYPE FORM and File ONE Copy)

API # Drilled 1946 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR John J. Darrah, Jr. KCC LICENSE # 5088  
(owner/company name) (operator's)

ADDRESS 225 N. Market #300 CITY Wichita

STATE KS ZIP CODE 67202 CONTACT PHONE # (316) 263-2243

LEASE RATHBUN A WELL# 1 SEC. 16 T. 17 R. 8 W (East West)

SW SE SE SPOT LOCATION/0000 COUNTY Ellsworth

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM S/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE none SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 216 CEMENTED WITH 140 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3241 CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4" liner 1265 OH 3241-3247

ELEVATION 1721 KB T.D. 3247 PFTD \_\_\_\_\_ ANHYDRITE DEPTH 2790  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Tubing to 3100, Pump 35sx 60-40 poz 10% gel, Pull tubing to 1050, perf 1075, pump 35 sx AA, pull tuning to 725, perf 750, pump 35 sx AA, pull all tubing, Pump 25 sx 4"-5 1/2, pump 100 sacks in 4 1/2.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? yes  
If not explain why? has been filed

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
G.P. Stoepfelwerth PHONE# (620) 786-4046

ADDRESS above City/State \_\_\_\_\_

PLUGGING CONTRACTOR to be determined Classic Well Service KCC LICENSE # 32098  
(company name) (contractor's)

ADDRESS Box 539 Chaffin, KS 67525 PHONE # ( ) \_\_\_\_\_

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) as equipment available 11/08/06 - 10:00 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: Nov. 2, 2006 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

\*Well is already plugged - KCC-Dlg

Dist 02

RECEIVED  
NOV 8 2006  
11-8-2006  
KCC WICHITA