

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K A R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: F. G. Holl Company, L.L.C.

Address: 9431 E Central, Suite 100, Wichita, KS 67206

Phone: (316) 684-8481 Operator License #: 5056

Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 185-22,771 - 00 - 00

Lease Name: Biggs

Well Number: 1-15

Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - NW  
4950 Feet from  North /  South Section Line

4950 Feet from  East /  West Section Line

Sec. 15 Twp. 24 S. R. 15  East  West

County: Edwards

Date Well Completed: 5-19-91 Per RBDMS

Plugging Commenced: 11-24-06 PKT 12/28/06

Plugging Completed: 11-27-06 KCC

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	268	
				4 1/2	4234	<u>2040-2000'</u> <u>KCCPKT</u> <u>PERCP-13</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4000', bailed 4 sacks cement with bailer, pulled slips, had 19" stretch, ripped casing at 2210', worked pipe, ripped casing at 2040', pipe came free, pulled casing up to 1000', pumped 15 gel-50 sacks cement, pulled to 300', pumped 50 sacks, pulled to 40', pumped 20 sacks to surface, pulled joint, tore down floor & rig, emptied pit.

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 401 W Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: F.G. Holl Company, L.L.C.

State of Kansas County, Sedgwick, ss.

Loveness Mpanje (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Loveness Mpanje

(Address) 9431 E. Central, Suite 100, Wichita, Kansas 67206

Betty H. Spotswood SUBSCRIBED and SWORN TO before me this 21st day of December, 2006, at \_\_\_\_\_, 20  
Betty H. Spotswood

My Commission Expires: 04/30/2010

Notary Public



Maple Grove Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 22 2006  
CONSERVATION DIVISION  
WICHITA, KS