

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: F. G. Holl Company, L.L.C.

Address: 9431 E Central, Suite 100, Wichita, KS 67206

Phone: (316) 684-8481 Operator License #: 5056

Type of Well: Oil/Gas KCC Per CP 213 PKT 12/28/06
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) Docket #: _____ (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 007-22,673-0000

Lease Name: Hicks-Johnson

Well Number: 1-10

Spot Location (QQQQ): _____ - NE - NE - NW

330 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 10 Twp. 30 S. R. 14 East West

County: Barber

Date Well Completed: 12/4/01 Per RBDM

Plugging Commenced: 11-27-06 PLG

Plugging Completed: 11-29-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	231	
				4 1/2	3507	2230

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off bottom, loaded casing with water, sand was at 3050', bailed 4 sacks cement with bailer, dug cellar, set floor, pulled slips, cut surface off 4' below ground, had 20" stretch, ripped casing at 2410', worked pipe, ripped casing at 2230', worked pipe free, pulled casing up to 800', swedge in, pumped 12 gel & 50 sacks cement, pulled to 260', pumped 100 sacks, pulled to 40', pumped 40 sacks to surface, pulled joint, cleaned up location.

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 401 W Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: F. G. Holl Company, L.L.C.

State of Kansas County, Sedgwick, ss.

Loveness Mpanje (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Loveness Mpanje

(Address) 9431 E. Central, Suite 100, Wichita, Kansas 67206

My Appointment Expires 4/30/2010
SUBSCRIBED and SWORN TO before me this 21st day of December, 2006, 20

My Commission Expires: 04/30/2010

Notary Public



RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DEC 22 2006

CONSERVATION DIVISION
WICHITA, KS