

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Exxon Mobil Oil Corporation
Address: PO Box 4358 Houston TX 77210
Phone: (281) 364 5073 Operator License #: 5208
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-13-06 (Date)
by: Richard Lacy (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2786' Bottom: 2883' T.D. 3040'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-093-20513-0000
Lease Name: USA White Unit D
Well Number: D-2 ICC Per CP 2/3 PRT
Spot Location (QQQQ): _____ - _____ - C-NW Senw 12/28/06
1346 Feet from North / South Section Line PER
1417 Feet from East / West Section Line RBPW
Sec. 17 Twp. 26 S. R. 35 East West
County: Kearny
Date Well Completed: 9-1-78
Plugging Commenced: 9-14-06
Plugging Completed: 9-14-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	823'	8 5/8	823	-
Production		0	3040'	5 1/2	3040	929

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 400 lb. hulls & 25 sx cmt to plug perfs from 2786 to 2586. Back off 5 1/2 @ 929 & pull to 860 Circ. hole w/mud 50 sx 860 to 710 30 sx 400 to 300 10sx 40-0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: EXXON MOBIL PROD CO.
State of KANSAS County, STEVENS, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 20 2006

(Employee of Operator) or (Operator) on above-described well, being first to sign, sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC, State of Kansas (Signature) R B Beem
DORETTA L. DELAY
My Appt. Exp. 12-27-08 (Address) 200 W 4th HUGOTON KS 67951

SUBSCRIBED and SWORN TO before me this 16 day of November, 20 06
Doretta L. Delay My Commission Expires: 12-27-08
Notary Public

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

regulatory contact: Jacqueline Davis 12/19/06 281-654-1913 PRT