

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berry Petroleum Company  
Address: P. O. Box 250, Wray, CO 80758  
Phone: (970) 332-3585 Operator License #: 33116

Type of Well: Gas Docket #: NA  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9/04/06 (Date)  
by: David P. Williams (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
NBRR Depth to Top: 1280 Bottom: 1304.3 T.D. 1551 *Per RBDMS PPT*  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-181-20387-00-00  
Lease Name: R. Helman  
Well Number: 24-13 6S40W  
Spot Location (QQQQ): \_\_\_\_\_ - S/2 - SE - SW  
376 Feet from  North /  South Section Line  
2063 Feet from  East /  West Section Line  
Sec. 13 Twp. 6S S. R. 40  East  West  
County: Sherman  
Date Well Completed: 1/11/06  
Plugging Commenced: 12/04/06  
Plugging Completed: 12/04/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Bentonite	Gas	Surface	404	7"	397'	-0-
NBRR	Gas	<u>1280</u> <u>1565'</u>	1304	4-1/2"	1559'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU Allied & Excel. Blow well down. Take off frac valve & install cementing head.  
Mix & pump down 4-1/2", 75 sks 60/40 POS cement w/ 10% gel & 450# of cotton seed hulls. Pressured up to 450#. SI.  
RU to pump down surface. Mix 40 sks 60/40 POS cement w/ 50# cotton seed hulls & pump down 7" surface csg.

Pressured up to 200#. SI. Witnessed by Daryl Dipman of KCC. RDMO Allied & Excel. Cut off csg. 5' below GL & weld on cap.

Name of Plugging Contractor: Advanced Drilling Technologies LLC License #: 445725 33532 *KCC Per CPA/B*  
Address: P. O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Berry Petroleum Company

State of Colorado County, Yuma, ss.

Wayne S. King (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Wayne Kj  
(Address) P. O. Box 250, Wray, Colorado 80758

SUBSCRIBED and SWORN TO before me this 5th day of DECEMBER, 2006

Mary C. Twiss My Commission Expires: \_\_\_\_\_  
Notary Public My Comm. expires 3-12-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
DEC 19 2006  
KCC WICHITA

# ALLIED CEMENTING CO., INC. 25450

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
OAKLE, KS

DATE <u>12-4-06</u>	SEC <u>13</u>	TWP. <u>69</u>	RANGE <u>40 W</u>	CALLED OUT	ON LOCATION <u>9:00 AM</u>	JOB START <u>11:30 AM</u>	JOB FINISH <u>12:00 PM</u>
LEASE <u>R. Helman</u>		WELL # <u>24.13</u>		LOCATION <u>Goodland N. Rd 78</u>		COUNTY <u>SHAWNEE</u>	STATE <u>KS</u>
OLD OR NEW (Circle one) <u>OLD</u>				<u>2 W. 1 S. 1/2 E 2</u>			

CONTRACTOR <u>None</u>	OWNER
TYPE OF JOB <u>AWP</u>	
HOLE SIZE	T.D.
CASING SIZE <u>4 1/2</u>	DEPTH <u>1564'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS. <u>1231-1303'</u>	
DISPLACEMENT	

CEMENT	
AMOUNT ORDERED <u>125 60/40 109</u>	
<u>col. 400' hulls</u>	
<u>(used 115-22)</u>	

COMMON <u>69</u>	@
POZMIX <u>46</u>	@
GEL <u>10</u>	@
CHLORIDE	@
ASC	@
<u>Cottonseed Hulls 4</u>	@
	@
	@
	@
	@
	@
HANDLING <u>140</u>	@
MILEAGE <u>.09 1/2 mile</u>	

**EQUIPMENT**

PUMP TRUCK	CEMENTER <u>Fuzzie</u>
# <u>102</u>	HELPER <u>Sam</u>
BULK TRUCK	
# <u>315</u>	DRIVER <u>Alan</u>
BULK TRUCK	
#	DRIVER <u>Alan</u>

**REMARKS:**

M. 75 lbs cement with 55# hulls  
down 4 1/2 csg. 150' skid in pipe  
50# hulls  
M. 40 lbs cement down 1/2 csg. to  
200' skid in pipe  
Subsample @ 12:00 PM (CT)  
Trucks Fuzzie + crew

TOTAL

**SERVICE**

DEPTH OF JOB <u>1303'</u>	
PUMP TRUCK CHARGE	
EXTRA FOOTAGE	@
MILEAGE <u>.09</u>	@
MANIFOLD	@
	@
	@

TOTAL

CHARGE TO: Berry Production

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

	@
	@
	@
	@
	@

TOTAL

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME