

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Exxon Mobil Oil Corporation  
Address: PO Box 4358 Houston TX 77210  
Phone: (281) 364 5073 Operator License #: 5208  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 9-27-06 (Date)  
by: Richard Lacy (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Herrington Depth to Top: 2599 Bottom: 2608 T.D. 2775'  
u. Kridgr Depth to Top: 2628 Bottom: 2646 T.D. "  
L. Kridgr Depth to Top: 2654 Bottom: 2676 T.D. "  
Winfield Depth to Top: 2701 Bottom: 2716 T.D. "

API Number: 15-175-00464-00-00  
Lease Name: Hopkins Estate Unit  
Well Number: 1  
Spot Location (QQQQ): - NW - NW - SE  
2640 Feet from  North /  South Section Line  
2640 Feet from  East /  West Section Line  
Sec. 3 Twp. 31 S. R. 33  East  West  
County: Seward  
Date Well Completed: 11-1-50  
Plugging Commenced: 10-2-06  
Plugging Completed: 10-3-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	705'	10 <sup>3</sup> / <sub>4</sub>	705	-
production		0	2775'	6 <sup>5</sup> / <sub>8</sub>	2775	-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2<sup>3</sup>/<sub>8</sub> to 2500 (@ fill) Circ. hole w/mud 35 sx 2500 to 2300  
(6<sup>5</sup>/<sub>8</sub> was circ. w/cmt) 35 sx 1700 to 1500 45 sx 730 to 530  
10 sx 40 to 0 Cut off 10<sup>3</sup>/<sub>4</sub> & 6<sup>5</sup>/<sub>8</sub> & capped 10<sup>3</sup>/<sub>4</sub> 3 ft.  
below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: EXXON MOBIL PROD Co.  
State of KANSAS County, STEVENS, ss.

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 19 2006

RICHARD B. LEWIS (Employee of Operator) or (Operator) on above described well, duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well, and the same are true and correct, so help me God.

NOTARY PUBLIC, State of Kansas  
DORETTA L. DELAY  
My Appt. Exp. 12-27-08

(Signature) RBL Lewis  
(Address) 200 W 4th HUGOTON KS 67981

SUBSCRIBED and SWORN TO before me this 16 day of November, 2006

Doretta L. Delay My Commission Expires: 12-27-08  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

regulatory contact: Jaqueline Davis

12/18/06

281-654-1913

PLG