

** corrected **

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20263-00-00
Spot: NESWSWE Sec/Twnshp/Rge: 5-20S-33W
646 feet from S Section Line, 2171 feet from E Section Line
Lease Name: HATTENDORF Well #: 2
County: SCOTT Total Vertical Depth: 4750 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION, INC.
Address: BOX 489 205 E. 7TH STREET, HADLEY
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4749	1178	WITH 180 SX CMT
SURE	8.625	437		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: AL Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4050' & 2 SX CMT. PLUG AT 1160' WITH 10 SX GEL & 75 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2006 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SAND BACK TO 4050' WITH 2 SX CMT. 1ST PLUG AT 1160' WITH 10 SX GEL & 75 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 440' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4718	4728		
4692	4696		
4684	4688		
4659	4663		
4645	4651		
4458	4462		
4392	4396		
4365	4370		

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND CEMENTING.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 27 2006
CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20263-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 5-20S-33W
600 feet from S Section Line, 550 feet from W Section Line
Lease Name: HATTENDORF Well #: 2
County: SCOTT Total Vertical Depth: 4750 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION, INC.
Address: BOX 489 205 E. 7TH STREET, HADLEY
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4749	1178	WITH 180 SX CMT
SURF	8.625	437		

\$ 154.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: AL Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4050' & 2 SX CMT. PLUG AT 1160' WITH 10 SX GEL & 75 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2006 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SAND BACK TO 4050' WITH 2 SX CMT. 1ST PLUG AT 1160' WITH 10 SX GEL & 75 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 440' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4718	4728		
4692	4696		
4684	4688		
4659	4663		
4645	4651		
4458	4462		
4392	4396		
4365	4370		

INVOICED
DATE 12-18-06
INV. NO. 2007061009

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND CEMENTING.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
DEC 15 2006
KCC WICHITA

RET