

4-060652

2-21 15-163-01523-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 2-1-49

NW NE NE /4 SEC. 16, 09 S, 17 W
4950 feet from S section line
990 feet from E section line

Operator license# 101 -

Lease Carmichael well # 2

Operator: State of Kansas - Fee Fund

County Rooks

Address: 2301 E. 13th Street
District #4 - Hays, Kansas
Jay Baker - Operator 67601

Well total depth 3502 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 366 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: State of Kansas - Fee Fund License#

Address:

Company to plug at: Hour: 9:45A.M. Day: 21 Month: February Year: 95

Plugging proposal received from: District #4 Staff

Company: Phone:

Were: Order 350 sxs. 60/40 posmix - 10% gel.

Tom's Welding - rebuilt wellhead for plugging.

Gordon Steckline - dig out well and restore location after plugging.

Halliburton Cementing.

Mercury Wireline - perforations.

Leo's Tank Service - water for cementing and empty pit.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:45A.M., Day: 21, Month: February, Year: 95

Actual plugging report: 8 5/8" to 366'. 5 1/2" to 3500'. Perforated
at 875' - 1375' - 1850'. Tied onto annulus and pumped 60 sxs. cement
with 100# hulls. Max. P.S.I. 150#. S.I.P. 50#. Tied onto production
casing and pumped 290 sxs. cement with 400# hulls. Max. P.S.I. 500#.
S.I.P. 125#. Well plugged as expected.

RECEIVED
STATE CORPORATION COMMISSION
3/14/95
MAR 14 1995
STATE CORPORATION COMMISSION
WICHITA, KANSAS

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2074 GL

I did[X] / did not[] observe the plugging. Herb Deines

(agent)