

9-12

2982

6-041327

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-01525-00-00

NE NE NW /4 SEC. 16 S. 9 W  
4950 feet from S section line  
2970 feet from E section line

KCCZAD

Operator license# 8133

Lease Yeagy well # X

Operator: William E. Hammerschmidt

County Rooks KCCZAD

Address: 900 S. Sec. Line  
Plainville, Kansas 67663

Well total depth 3458 feet 115.63  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00P.M. Day: 12 Month: September Year: 91

Plugging proposal received from: William E. Hammerschmidt

Company: William E. Hammerschmidt Phone:    

Were: 5 1/2" casing set at 3458' w/o sks. cement. Perfs. at 3118' to 3436'. Perf. anhy. at 1300'. Perf. base dakota at 650'. W.H.M. 3430'. Ordered 325' sks. 60/40 poz. - 10% gel. w/1/4 lb. flocele plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All  ], Part  ], None  ]

Completed: Hour: 6:00P.M., Day: 12, Month: September, Year: 91

Actual plugging report: Pumped in 5 1/2" casing w/25 sks. cement w/1/4 lb. flocele plus pumped in additional 250 sks. cement w/1/4 lb. flocele and 300# hulls mixed in cement. Max. 400 lb. S.I. 200 lb. Pumped in 8 5/8" casing w/50 sks. cement w/1/4 lb f.c. and 200# hulls mixed in cement. Max. 500 lb. S.I. 200 lb.

RECEIVED  
KANSAS CORPORATION COMMISSION

10/8/91  
OCT 8 1991

Remarks:    

CONSERVATION DIVISION  
WICHITA, KS

I did  / did not  observe the plugging.

Dennis L. Hamel

INVOICED

DATE 10-16-91  
INV. NO. 33360

Gib. S.

(agent)  
Form CP-2/3