

4-070095

S-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,622-00-00

SW SE NE /4 SEC. 31, 09 S, 17 W
2970 feet from S section line
990 feet from E section line

Operator license# 5900

Lease: Schrandt Well # 1

Operator: Lawbanco Drilling, Inc.

County: Rooks 115,96

Address: P.O. Box 289
Natoma, Kansas 67651

Well total depth 3568 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 175 feet
W/120 sxs.

ABAND. oil well X, Gas well, Input well, SWD., D&A

Plugging contractor: Lawbanco Drilling Company License# 5900

Address: P.O. Box 289 - Natoma, Kansas 67651

Company to plug at: Hour: 5:00 A.M. Day: 8 Month: May Year: 1998

Plugging proposal received from: Virgil Dreiling

Company: Lawbanco Drilling Company Phone: 785-885-4676

Were: 8 5/8" set at 175' w/120 sxs common. 4 1/2" set at 3567'w/375 Halliburton Light.
W.L. 3560' Fluid Level 3200'. Perfs 3244.5 to 3565'. 41 perforations.
Ordered out 275 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 7:00 P.M., Day: 8, Month: May, Year: 1998

Actual plugging report: Allied pumped 200 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 200#. Pumped 50 sxs down backside. Max. P.S.I. 400#.
S.I.P. 100#.

Remarks:

Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: 2097 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

INVOICED

DATE MAY 14 1998

INV. NO. 50560

5-13-98

Form CP-2/3