

4-041937

9-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,100-00-00

C NE SW /4 SEC. 32, 09 S, 17 W
1980 feet from S section line
3300 feet from E section line

Operator license# 31670
Operator: Leo Hammerschmidt
Address: Box 426
Plainville, Kansas 67663

Lease: Ganoung 'A' Well # 1
County: Rooks 115.77
Well total depth 3562 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 206 Feet
W/105 sxs cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____
Address: Russell, Kansas 67663

Company to plug at: Hour: P.M. Day: 30 Month: September Year 1997

Plugging proposal received from: DENNIS HAMEL

Company: Leo Hammerschmidt Phone: _____

Were: 4 1/2" casing set at 3464' w/N/A sxs cement.
Holes in casing at 800' to 1300'.
Ordered 175 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - 10 sxs gel.

11-5-97

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[_____], None[_____]

Completed: Hour: 4:00 P.M., Day: 30, Month: September, Year: 1997

Actual plugging report: R.I.H. with tubing at 3400'. Spotted 10 sxs gel, followed with 50 sxs cement with 200# hulls. Pulled to 1800' - spotted 90 sxs cement with 100# hulls to circulate at surface. P.O.O.H. with tubing and squeezed casing with 10 sxs cement. Max. P.S.I. 300#. 8 5/8" - squeezed 25 sxs with 100# hulls. Max. P.S.I. 300#.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD Anhy.plugin: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: _____ G.L.

I did[] / did not[_____] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

NOV 06 1997

DATE _____

INV. NO. 49446

100-