

4-110096

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-20,266-00-00

NE SE SE / 4 SEC. 32, 09 S, 17 W  
990 feet from S section line  
330 feet from E section line

6/8

Operator license# 5252

Lease: Hilgers Well # 1

Operator: R.P. Nixon Operations, Inc.

County: Rooks 116.64

Address: 207 West 12<sup>th</sup> Street  
Hays, Kansas 67601

Well total depth 3589 feet  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 201 feet

Aband. oil well X, Gas well       , Input well       , SWD       , D & A       

Plugging contractor: R.P. Nixon Operations, Inc. License# 5252

Address: 207 West 12<sup>th</sup> Street - Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 8 Month: June Year: 2000

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: 785-628-3884

Were: Plug according to KCC Rules & Regulations.  
Ordered 350 sxs cement - 700# hulls.  
Plug thru casing.

RECEIVED  
KANSAS CORP COM  
200 JUN 15 P 4:21  
6-15-2000

Plugging Proposal Received by: Roger Moses

Plugging operations attended by agent? All [ X ], Part [    ], None [    ]

Completed: Hour: 12:30 P.M., Day: 8, Month: June, Year: 2000

Actual plugging report: 8 5/8" S.P. at 201' w/150 sxs cement. 5 1/2" casing at 3587' w/150 sxs cement. Perforated at 250' - 850' - 1400' and 1750'. Tied to 5 1/2" and pumped 100 sxs cement with 400# hulls, then 200 sxs cement with 300# hulls to Max. P.S.I. 700#.  
S.I.P. 300#. Tied to 8 5/8" x 5 1/2" annulus and pumped 50 sxs to Max. P.S.I. 300#.  
S.I.P. 100#. Total of 350 sxs 60/40 pozmix with 10% gel and 700# hulls.  
Dakota at 400' - 750'. Anhy at 1374' - 1411'. Salt at 1650' - 1750'.

Remarks: Allied Cementing. Leo's Tank Service

Condition of casing(in hole): GOOD X BAD        Anhy.plug: YES X NO         
Bottom plug(in place): YES       , CALC       , NO        Dakota plug: YES X, NO         
Plugged through TUBING       , CASING X Elevation: 2111 GL

I did [ X ] / did not [    ] observe the plugging.

Roger S. Moses  
(agent)

INVOICED  
DATE 6/16/00  
INV. NO. 61877

Form CP-2/3

R

ARMSTRONG-JACKMAN & ASPEN  
 GREAT BEND, KS.

#1 HILGERS

32-9-17W  
 NE SE SE

Contr. ASPEN DRLG. CO.

Cty. ROOKS

Geol. BOB ARMSTRONG

Pool NETTIE EXT.

E. 2116 KB Cm. 11/11/69 Cp. 12/31/69 IP PMP 25 BOPD +80%


API 15-163-20,266

WTR/TOR 3246-49  
 LANS 3275-3495

LOG Tops	Depth	Datum
*ANH	1374	+ 742
*B ANH	1411	+ 705
TOP	3012	- 896
HEEB	3228	-1112
TOR	3245	-1129
LANS	3268	-1152
BKC	3488	-1372
ARB	3570	-1454
LTD	3583	-1467
RTD	3589	-1473

Csg. 8" 201/150 sx; 5 1/2" 3587/150  
 DST 3238-70/60", 55' MD/SP OIL,  
 BHP 1150-1115#/30", FP 35-  
 75#  
 PF 6/3246-49, 4/3275-77, 4/  
 3304-06, 6/3324-27, 4/3349-51,  
 4/3360-62, 4/3369-71, 4/3406-  
 08, 4/3412-14, 24/3430-36,  
 24/3450-56, 4/3473-76, 4/  
 3493-95, 19,500 ACID, SWB PT  
 LD & POP

NO CORES

\*DRILLER'S TOPS  
 INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS