

4-060629

12-12

15-163-20261-00-02

D-21,831

API number: 15- - 1-7-70

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NE /4 SEC. 32 , 09 S, 17 W
3630 feet from S section line
330 feet from E section line

Operator license# 5252

Lease Becker OWWO well # 1

Operator: R.P. Nixon Operations, Inc.

County Rooks

Address: 207 W. 12th Street
Hays, Kansas 67601

Well total depth 1480 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 209 feet

48.10

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 11:00A.M Day: 12 Month: December Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: 913-628-3834

Were: Order 150 sxs. 60/40 posmix - 8% gel and hulls.
Prior history - Sanded back to 2500' from T.D. Squeeze holes from 933' -
1154' with 400 sxs. cement - perf. at 410' and squeeze with 115 sxs. to
900# - perf. at 598' and squeeze with 120 sxs. to 1200#. Drilled out
to 1130' with cement and plug at 1480'. Perf Cedar Hill 1066' - 1086'
20' with 2 S.P.F. Total 40 shots.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:45A.M, Day: 12, Month: December, Year: 94

Actual plugging report: 8 5/8" to 209' w/160 sxs. 5 1/2" to 3596'
w/150 sxs. P.B.T.D. 1480'. Annulus cemented to surface. Tied onto
casing and pumped 150 sxs. cement with 500# hulls. Max. P.S.I. 500#.
S.I.P. 500#.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
DEC 27 1994
12-27-94

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2110 GL

I did X / did not observe the plugging.

(agent)

Form CP-2/3

INVOICED

DATE 1-4-95

INV. NO. 41955

DA