

40

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE

12-27-61

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: CNW NW Sec. 32 Twp. 9 Rge. (E) (W) 17

Name of Field: _____ Total Depth: 3620

I have this date completed supervision of plugging of:

Lease Name: Eads Well No. B-1

Operator's Full Name: Davis Bros

Complete Address: 5 1/2 E 3rd Tulsa, Okla

Plugging Contractor Transit Corp

Address: Oklahoma City, Okla License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No X

If Yes how long? _____ Reason: _____

Operation Completed: Hour 9PM Day 21 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 205' circulated with cement.

Circulated hole with heavy mud - set cementing plug at 550', displaced 20
sax cement through drill pipe, heavy mud to 180', set cementing plug and
15 sax cement, heavy mud to 35', set plug, 1/2 sack hulls and filled to
bottom cellar with cement.

Signed: Edson Perry

Conservation Division Agent

Reviewed: Harold Morris
Field Supervisor

Remarks:

INVOICED

DATE 1/22/62

INV. NO. 4330-W