

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20714-00-00
Spot: SENE SW Sec/Twnshp/Rge: 17-9S-32W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: STEINLE Well #: 1-17
County: THOMAS Total Vertical Depth: 4700 feet

Operator License No.: 4629
Op Name: BRITO OIL COMPANY, INC.
Address: PO BOX 104
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253		

\$152.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/21/2006 8:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 12/21/2006 10:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug a 2640' w/25 sxs.
2nd. Plug at 1825' w/100 sxs.
3rd. Plug at 305' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED
DATE 12-29-06
INV. NO. 2007061038

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 26 2006

CONSERVATION DIVISION
WICHITA, KS

DEC 22 2006

RET