

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21251-00-00
Spot: E2E2W2SW Sec/Twnshp/Rge: 7-34S-18W
1320 feet from S Section Line, 1200 feet from W Section Line
Lease Name: HOFFMAN TRUST Well #: 2
County: COMANCHE Total Vertical Depth: 496 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	40		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/27/2006 11:15 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: STEVE EZELL Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: DRILL OUT REDI-MIX THAT WAS DUMPED ON TOP OF HOLE. WASHDOWN OLD HOLE TO 200'.
CIRCULATE CMT DOWN DRILL PIPE AND BACK TO SURFACE. MINIMUM OF 300 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2006 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:


Perfs:

11/27/06: STARTED DRILLING CMT AT 11:15. DRILLED THROUGH CMT AT 42'.
WASHED DOWN TO 155' WITH MUCH TROUBLE WITH BIT PLUGGING. LAID
DOWN DRILL PIPE AND SDON. 11/28/06: STARTED IN 2 3/8" TUBING. MIXED 16
SX GEL IN PIT AND WASHED DOWN TO 220'. PUMPED 400# HULLS, 175 SX CMT.
CIRCULATED 15 SX CMT TO PIT. TOPPED OFF WITH 12 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Eric MacLaren

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 26 2006

CONSERVATION DIVISION
WICHITA, KS