

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20712-00-00
Spot: NENESE Sec/Twnshp/Rge: 24-10S-34W
2125 feet from S Section Line, 550 feet from E Section Line
Lease Name: EPARD Well #: 1
County: THOMAS Total Vertical Depth: 4425 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S. MAIN PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253		

\$143.81

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/11/2006 6:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG UNREIN Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2435

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 12/11/2006 8:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2691' w/25 sxs.
2nd. Plug at 1671' w/100 sxs.
3rd. Plug at 303' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 12-29-06
INV. NO. 2007061035

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
DEC 21 2006

District: 04

Signed _____

[Signature]
(TECHNICIAN)

KCC WICHITA

DEC 18 2006

[Handwritten mark]