

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21494-00-00
Spot: W2W2SW Sec/Twnshp/Rge: 35-16S-30W
1320 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SNIDER Well #: 1
County: LANE Total Vertical Depth: 4571 feet

Operator License No.: 5104
Op Name: BLUE GOOSE DRILLING COMPANY, IN
Address: PO BOX 1413
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4244	0	WITH 130 SX CMT
SURF	8.625	221		WITH 140 SX CMT

\$148.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2006 2:10 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: _____ Phone: _____

Proposed Plugging Method: TOP OF FISH WITH 25 SX CMT. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2006 5:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF FISH @ 2650'. 1ST PLUG AT 2635' WITH 25 SX CMT. 2ND PLUG AT 2150' WITH 90 SX CMT. WENT ON VACUUM. 3RD PLUG AT 1200' WITH 500# HULLS & 70 SX CMT. 4TH PLUG AT 120' WITH 50 SX CMT. CMT CIRCULATED. PRESSURED BACKSIDE WITH 15 SX CMT. MAXMUM PRESSURE 500#.

Perfs:


Top	Bot	Thru	Comments
4152	4154		
3964	3968		

INVOICED
DATE 12-29-06
INV. NO. 2007061034

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01



Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
DEC 20 2006
KCC WICHITA

Form CP-223
[Handwritten signature]