

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20065-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 8-12S-17W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KARLIN Well #: 4
County: ELLIS Total Vertical Depth: 3703 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3585	0	75 SX
SURF	8.625	168	0	140 SX

\$ 120.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DAVE HEIN Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 600# hulls.
CIBP at 3500'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2006 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1900' - 1375' - 800'.
Hooked up to the annulus - mixed and pumped 50 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Swaged onto 5 1/2" - pumped 300 sxs cement with 600# hulls.
12/22/2006 - Topped well off with 25 sxs.

Perfs:

Top	Bot	Thru	Comments
3544	3548		
3462	3468		

INVOICED
DATE 12-29-06
INV. NO. 2007061037

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 28 2006

CONSERVATION DIVISION
WICHITA, KS

DEC 26 2006

PK

ISERN-WELLS

#4 KARLIN

8-12-17W
APP C NW SW SE

Contr. ISERN DRLG

Cty. ELLIS

Geol.

Pool BEMIS-SHUTTS

E. 2132 KB Cm. 5/16/67 Cp. 6/29/67 IP PMP 30 BOPD + 24%
WTR/LANS 3462-68

LOG Tops	Depth	Datum	Csg.
ANHY	1348	+ 784	API 15-051-20,065
TOP	3185	-1053	8" 168/140 sx 5" 3585/75 sx
HEEB	3323	-1191	DST 3436-70/1', 1200' GIP, 210'
TOR	3344	-1212	HO&GCM, 60' MDY OIL, BHP 291-
LANS	3372	-1240	291#/30", FP 41-124#;
CH CONG	3619	-1487	DST 3275-3317 (STRAD) 30", 30'
			WTRY MUD, FBHP 933#/20", FP
			33-33#;
			CO 3650, PF /3544-48, A 2000, DID
LTD	3701	-1569	NOT REC LOAD, SET BP @ 3500, PF /
RTD	3703	-1571	3462-68, A 2500, SWB 6 BFPH, 20%
			OIL, POP, PB TD 3500.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS