

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20143-00-00
Spot: NESENW Sec/Twnshp/Rge: 19-12S-17W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ANNA KRANNAWITTER Well #: 4
County: ELLIS Total Vertical Depth: 3635 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3633	0	125 SX
SURF	8.625	249	0	150 SX

H 118.14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2006 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DAVE HEIN Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 775' - 1350' - 1850'.
Hooked up to the annulus - mixed and pumped 15 sxs cement.
S.I.P. 700#.
TIH with tubing to 3000' - mixed and circulated cement with 180 sxs with 500# hulls.
POOH. Swaged onto 5 1/2" and topped with 70 sxs cement.
Max. P.S.I. 700#. S.I.P. 400#.

Perfs:

INVOICED
DATE 12-29-06
INV. NO. 2007061037

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

DEC 26 2006

DEC 28 2006
CONSERVATION DIVISION
WICHITA, KS

Handwritten initials

