

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20231-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 18-12S-17W  
990 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: I SCHMEIDLER Well #: B-2  
County: ELLIS Total Vertical Depth: 3671 feet

Operator License No.: 7383  
Op Name: BOLDING, GRADY CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3671	0	w/75 sxs cmt
SURF	8.625	241	0	w/150 sxs cmt

\$ 119.31

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2006 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DAVE HEIN Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2006 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1900' - 1375' - 825'.  
TIH with tubing to 3000' - mixed and circulated cement with 170 sxs cement and 500# hulls.  
POOH. Swaged onto 5 1/2" - topped with 80 sxs cement.  
Max. P.S.I. 800#. S.I.P. 500#.  
Hooked up to the annulus and instant 600#.

Perfs:

**INVOICED**  
DATE 12-29-06  
INV. NO. 2007061037

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**DEC 28 2006**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

DEC 26 2006

ELLIS BEVER #B-2 I. SCHMEIDLER 18-12-17W  
NW SE SW

Contr. SAGE DRLG. Cty. ELLIS

Geol. WARREN JOHNSON Pool BEMIS-SHUTTS

E. 2134 KB Cm. 3/27/68 Cp. 4/25/68 IP P 25 BOPD/ARB  
3671-74


AP: 15-051-20,231

SMP Tops	Depth	Datum
ANHY	1345	+ 789
FOP	3101	- 967
HEEB	3340	-1206
LANS	3387	-1253
CONG	3633	-1499
SP SH	3652	-1518
ARB	3667	-1533
RTD	3671	-1537
DDTD	3674	-1540

Csg. 8" 241/150 sx, 5" 3671

NO DST'S, CO & DD 3674 TD, ACID  
500, SWB PT LD, POP.

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS