

API NUMBER 15-163-01525-00-00

LEASE NAME Yeagy

WELL NUMBER #X2

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 16 TWP. 9 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 9-12-91

Plugging Completed 9-12-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR William E. Hammerschmidt

ADDRESS 900 S. Section line

PHONE# (913) 434-2403 OPERATORS LICENSE NO. 8133

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 12, 1991 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE OF KANSAS
Received
11/14/91
NOV 14 1991
CORPORATION DIVISION
Wichita Kansas

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
5 1/2" casing set at 3458' w/ 10 sks. cement. Perfs. at 3118' to 3436'. Perf. ann. at 1300'. Perf. base dakota at 650'. W.H.M. 3430'. Ordered 325' sks. 60/40 pag. - 10% gel. w/ 1/4" hr. floccle. plus 500# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: William E. Hammerschmidt

STATE OF Kansas COUNTY OF Rooks, ss.

William E. Hammerschmidt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William E. Hammerschmidt

(Address) same



SUBSCRIBED AND SWORN TO before me this 24 day of Nov, 1991

Betty Edson Notary Public

My Commission Expires: Jan 26, 1992

Pumped in $5\frac{1}{2}$ " casing w/ 25 sks. cement w/ $\frac{1}{4}$ lb. ylocels
plus pumped in additional 250 sks cement w/ $\frac{1}{4}$ lb.
ylocels + 300# hulls mixed in cement. Max 400 lb. S.I. 200 lb.
Pumped in $8\frac{5}{8}$ " casing w/ 50 sks. cement w/ $\frac{1}{4}$ lb. f.c. + 200#
hulls mixed in cement. Max 500 lb. S.I. 200 lb.