

15-163-02947-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rocks _____ County. Sec. 16 Twp. 9S Rge. (E) 17 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE NE

Lease Owner The Derby Oil Company - Peel-Hardman Producers

Lease Name Carmichael Well No. 3

Office Address P.O. Box 1030, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 18 1949

Application for plugging filed May 18 1949

Application for plugging approved May 18 1949

Plugging commenced May 18 1949

Plugging completed May 18 1949

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. R. Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3510 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	395'	8 5/8"	395'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3510' - 395 1/2' - Heavy Rotary Mud
 395 1/2' - 394' - Wooden Plug
 394' - 356 1/2' - 15 sacks cement
 356 1/2' - 36 1/2' - Heavy Rotary Mud
 36 1/2' - 35' - Wooden Plug
 35' - 6' - 10 sacks cement and rock
 6' - surface - Cellar

RECORDED
 Conservation Div.
 5/31/49
 MAY 31 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to The Derby Oil Company
Address P.O. Box 1030, Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Glenn Peel Drilling Company, Inc. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN PEEL DRILLING COMPANY, INC.

(Signature) *[Signature]*
P.O. Box 359, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd. day of May, 1949

My commission expires June 4, 1951 *[Signature]* Notary Public.



DRILLER'S LOG

Company: The Derby Oil Company
Peel-Hardman Producers

Sec. 16 Twp. 9S Rge. 17W
NE NE NE

Farm: Carmichael Well No. 3
Total Depth: 3510'
Comm.: 5-11-49 Comp.: 5-18-49
Contractor: Glenn Peel Drilling Co., Inc.
Casing:
8 5/8" 395' cem.

County: Rooks,
Kansas

Elevation:

Production: Dry

Figures below indicate bottom of formations

Clay and Rock	0 -	40
Sand and Shale		65
Shale and Shells		395
Sand		1060
Shale and Shells		1320
Anhydrite		1365
Shale and Shells		1775
Broken Line		2070
Line and Shale		2275
Broken Line		2490
Line		2605
Shale and Line		2785
Broken Line		2915
Line		3510
Total Depth		3510

RECEIVED
Conservation Div.
5/31/49
MAY 31 1949
STATE CORPORATION
COMMISSIONER
KANSAS

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING COMPANY, INC.

BY: J. B. Anderson

SUBSCRIBED AND SWORN to before me this 23rd. day of May, 1949

My commission expires June 4, 1951

Marion M. Hecker
Notary Public

PLUGGING
MAY 16 9 17 AM
ROOKS CO. 98