

STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 32 Twp. 9S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Davis Bros.-Transit Corporation
Lease Name Eads "B" Well No. 1
Office Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 21, 1961 19
Application for plugging filed December 21, 1961 19
Application for plugging approved December 21, 1961 19
Plugging commenced December 21, 1961 19
Plugging completed December 21, 1961 19
Reason for abandonment of well or producing formation No Production

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 550', set plug, cemented with 20 sacks
Filled hole with heavy drilling mud to 180', set plug, cemented with 15 sacks
Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks
to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1962
1-25-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

SUBSCRIBED AND SWORN TO before me this 10th day of January, 1962

(Address) _____
Paul E. Goshens
Notary Public.

My commission expires 1-3-66



DRILLER'S WELL LOG

Davis Bros.-Transit Corporation

Eads "B" # 1 well, located in
C NW NW, Section 32-9S-18W, 14W
Rooks County, KansasCommenced: December 8, 1961
Completed: December 21, 1961
Elevation: 2121' KBCasing: 8 5/8" @ 203'
Cemented w/125 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface soil	0	75
Sand streaks	75	105
Shale	105	203
Shale and shells	203	510
Sand	510	630
Shale	630	965
Sand and shale	965	1187
Shale	1187	1325
Shale and Red Bed	1325	1420
Anhydrite	1420	1458
Shale	1458	1805
Salt	1805	1920
Shale	1920	1950
Shale w/lime	1950	2095
Lime and shale	2095	2380
Lime w/shale streaks	2380	2655
Lime and shale	2655	2790
Shale w/lime	2790	2965
Shale	2965	3047
Lime and shale	3047	3095
Lime	3095	3200
Lime and shale	3200	3285
Lime	3285	3605
Cherty lime, shale and Simpson Dolomite	3605	3632
Arbuckle	3632	3660 TD

RECEIVED
STATE CORPORATION COMMISSIONJAN 25 1962
1-25-62
CONSERVATION DIVISION
Wichita, KansasI hereby certify the foregoing to be a true and correct Driller's Log
of the formations encountered in the above well.Subscribed and sworn to before me
this 10th day of January, 1962

TRANSIT CORPORATION

By L. J. KruseMy commission expires 1-3-66Paul E. Gathers
Notary Public