


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Rooks County, Sec. 32 Twp. 9S Rge. 17 (E)W (W)

Location as "NE/CNW/SW" or footage from lines SW/4 SW/4 NE/4

Lease Owner Prime Drilling Co. & Davis Bros.

Lease Name Becker Well No. 1

Office Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-8 19 52

Application for plugging filed 7-8 19 52

Application for plugging approved 7-8 19 52

Plugging commenced 7-8 19 52

Plugging completed 7-8 19 52

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3625 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 190', set plug and cemented with 15 Sacks cement. Filled hole with heavy drilling mud to 40', set plug and cemented with 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1952
7-12-52
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 1516 Liberty Bank Building, Okla. City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss. L. J. Kruse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

Oklahoma City, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1952

Lillian Wright Notary Public.

My commission expires October 24, 1955

PLUGGING
327-9-176
NOV 29 1952

DAVIS BROTHERS & PRIME DRILLING COMPANY

SW/4 SW/4 NE/4 Section 32-9S-17W
Rooks County, Kansas

BECKER NO. 1

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Sand	0	68	8-5/8" C.S.A. Set @ 202'. Cemented with 135 Sacks Cement
Shale & Sand	68	215	
Shale Shells Sand	215	885	
Shale & Sand	885	1622	
Shale & Shells	1622	1842	
Shale & Sand	1842	1939	
Shale & Lime	1939	2250	
Lime & Shale	2250	2488	
Shale & Lime	2488	2555	
Lime & Shale	2555	2715	
Shale & Lime	2715	2940	
Shale	2940	3000	
Lime & Shale	3000	3080	
Lime	3080	3147	
Lime & Shale	3147	3243	
Lime	3243	3350	
Lime & Shale	3350	3389	
Lime	3389	3557	
Lime & Shale	3557	3571	
Lime	3571	3616	
Dolomite & Chert	3616	3625	
Total Depth		3625'	

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

PRIME DRILLING COMPANY

By: L. J. Kruse
 L. J. Kruse, Secretary

Subscribed and sworn to before me this 11th day of July, 1952.

Lillian Wright
 Notary Public

My Commission Expires:

October 24, 1955

RECEIVED

