

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-163-20512-00-01

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 3 TWP. 9 RGE. 18W ~~NE~~ W
Location as in quarters or footage from lines:
NW NE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Sterling Drilling Company
Lease Name Wildrix Well No. 1
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed March 27, 1974
Application for plugging filed April 18, 1983
Plugging commenced May 23, 1983
Plugging completed May 23, 1983
Reason for abandonment of well or producing formation
Not economical to operate.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation K.C. Depth to top 3208 bottom 3212 T.D. 3445
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	208	8 5/8	208	---
<u>K.C.</u>	<u>Oil</u>	<u>3208</u>	<u>3212</u>	<u>2 7/8</u>	<u>3361</u>	<u>240</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rigged up Allied Cementing Company and plugged well down
8 5/8" casing with 25 sacks 50/50 Pozmix, 1 sack hulls
mixed with cement - 30 sacks gel and 200 sacks 50/50
Pozmix, 6% gel, with 5 sacks hulls mixed with gel and
cement.

Plugging complete 5:30 PM, 5-23-83.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Olin Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Olin Kelso
Olin Kelso, Production Supt.
P. O. Box 129, Sterling, Kansas
(Address) 67579

SUBSCRIBED AND SWORN TO before me this 25th day of May, 19 83

Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85 STATE CORPORATION COMMISSION

RECEIVED
5/26/83
MAY 26 1983



DRILLERS LOG

WILDRIX #1

CASING RECORD: OPERATOR: Sterling Drilling Co. DESCRIPTION:
208' 8-5/8" CONTRACTOR: John O. Farmer, Inc. NW NE NW
Cemented w/150 sx. COMMENCED: February 18, 1974 Sec. 3-19-18W
TOTAL DEPTH: COMPLETED: March 1, 1974 Rooks County, Ks.
3445'


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	202	600
Shale & Sand	600	880
Sand	880	1105
Red bed	1105	1387
Anhydrite	1387	1425
Shale & Shells	1425	2040
Shale	2040	2235
Shale & Lime	2235	2360
Lime & Shale	2360	2470
Shale & Lime	2470	2635
Lime & Shale	2635	2845
Shale & Lime	2845	2960
Lime & Shale	2960	3208
Lime	3208	3445
Total Depth	3445'	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

JOHN O. FARMER, INC.

John O. Farmer III
John O. Farmer, III

Subscribed and sworn to before me this 6th day of March, 1974.



RECEIVED
STATE CORPORATION COMMISSION

5/11/83
MAY 11 1983

CONSERVATION DIVISION
Wichita, Kansas

Helen Carlson
Helen Carlson

15-163-205/2-00-01

DRILLERS LOG

WILDRIX #1

CASING RECORD: 208' 8-5/8"
Cemented w/150 sx.

OPERATOR: Sterling Drilling Co.

CONTRACTOR: John O. Farmer, Inc.

COMMENCED: February 18, 1974

COMPLETED: March 1, 1974

DESCRIPTION: NW NE NW
Sec. 3-19-18W
Rooks County, Ks.

TOTAL DEPTH:
3445'


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	202	600
Shale & Sand	600	880
Sand	880	1105
Red bed	1105	1387
Anhydrite	1387	1425
Shale & Shells	1425	2040
Shale	2040	2235
Shale & Lime	2235	2360
Lime & Shale	2360	2470
Shale & Lime	2470	2635
Lime & Shale	2635	2845
Shale & Lime	2845	2960
Lime & Shale	2960	3208
Lime	3208	3445
Total Depth	3445'	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

JOHN O. FARMER, INC.

John O. Farmer III
John O. Farmer, III

Subscribed and sworn to before me this 6th day of March, 1974.



Helen Carlson
Helen Carlson

My commission expires:
February 15, 1975

RECEIVED
STATE CORPORATION COMMISSION
5/26/83
MAY 26 1983
CONSERVATION DIVISION
Wichita, Kansas