

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: DaMar Resources, Inc.
Address: 234 W. 11th
Phone: (785) 625-0020 Operator License #: 9067
Type of Well: oil Docket #: ---
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/3/06 (Date)
by: Roger Moses (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3312 Bottom: --- T.D. 3390
Simpson Sand Depth to Top: 3304 Bottom: 3311 T.D. ---
Depth to Top: --- Bottom: --- T.D. ---

API Number: 15-051,02069 ^{00-00 P19}
Lease Name: Potter 'A' ^{KCC 12/29/06}
Well Number: 14 ^{per operator Vicky}
Spot Location (QQQQ): C - SW - SE - SW
330 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 20 Twp. 11 S. R. 16 East West
County: Ellis
Date Well Completed: 2/27/59
Plugging Commenced: 11/3/06
Plugging Completed: 11/3/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	982	0
				5 1/2	3390	1354 1342'

KCC PVT per CP 2/B


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing to bottom, spot 15 sx poz w/10% gel and 300# hulls, pull tubing. Cut 5 1/2" casing @ 1354, pull two joints casing, pump 150 sx 60/40 poz w/10% gel and 200# hulls @ approx. 1290' down casing, pull 34 joints casing, pump 35 sx down casing. Pull rest of casing. Hole standing full.

Name of Plugging Contractor: Express Well Service License #: 6426
Address: Victoria, KS 67671
Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.
State of Kansas County, Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) [Signature]
(Address) P.O. Box 70 Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 22 day of December, 2006



[Signature] My Commission Expires: 10-18-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 26 2006
CONSERVATION DIVISION
WICHITA, KS