

ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

K.A.A.K. - 02-3-111

API NUMBER 15-101-21,567-00-00

LEASE NAME E M Land

TYPE OR PRINT

WELL NUMBER #1

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 26 TWP. 19S RGE. 29W (X) of (W)

S2SESE
per ep 43

KCC 12/29/06

PKT Per RBDms

LEASE OPERATOR Whitetail Crude, Inc

COUNTY Lane

ADDRESS P O Box 544, Ness City, KS 67560-0544

Date Well Completed 1/28/91

PHONE (785) 798-3641 OPERATORS LICENSE NO. 31627

Plugging Commenced 12/13/06

Character of Well oil

Plugging Completed 12/13/06

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/12/06 (date)

Eric MacLaren (KCC District Agent's Name)

ACO-1 filed? unknown If not, is well log attached?

Producing Formation LKC Depth to Top Bottom T.D. 4620

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surf			259	8.625		
PC			2190			
Prod			4612	5.500		KCC PKT Per CP 1/3

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from feet to feet each set. Tied onto 5 1/2" & pumped 35 sks cement w/300# hulls. Pumped 16 sks gel spacer then 170 sks cement. Well would not stay pressured up. Pumped 30 sks cement down 8 5/8" then ordered more cement to top off casing. Pumped 20 more sks down 8 5/8" & shut in. Pumped 100 sks cement down 5 1/2" w/300# hulls. 5 1/2" still would not pressure up. Pumped 50 more sks cement down 5 1/2", pumped 5 sks cement to top off well. Job complete.


Name of Plugging Contractor Whitetail Crude, Inc License No. 31627

Address P O Box 544, Ness City, KS 67560-0544

Name of Party Responsible for Plugging Fees: Whitetail Crude, Inc

State of Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Mike J. Fritzler
(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 21st day of December, 2006

Debra Kerr

RECEIVED
KANSAS CORPORATION COMMISSION

My Commission Expires: 4/20/09

USE ONLY ONE SIDE OF EACH FORM

DEC 26 2006

Form CP-1
Revised 05-03

CONSERVATION DIVISION
WICHITA, KS

PKT