

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,976 -00-00

LEASE NAME HRABE "B"

WELL NUMBER #4-26

990 4290 Ft. from Section Line ^{KCC}

990 1650 Ft. from Section Line

SEC. 26 TWP. 08 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 8/1/96

Plugging Completed 8/5/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR GRAHAM-MICHAELIS CORP.

ADDRESS P.O. Box 247, Wichita, KS 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? No. If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8-5/8"	256'	None
	Production			4-1/2"	3449'	750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Sanded bottom to 3110'. dumped 4 sx cement down hole. Had 3" stretch. Shot @ 2,000' & 1250'. Pumped 110 sx of 60/40 poz mix w/10% gel down hole. Displaced to 800'. Cemented @ 950'. Shot casing @ 925' & 775'. Casing loose. Pulled to 750' & pumped 85 sx cement w/200# hulls. Pulled to 300'. Circ Cmt to surf w/60 sx od cmt & 100# hulls. Job Complete 8/5/96
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mikes Testing & Salvage License No. ?

Address P.O. Box 209 Chase, KS 67524

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corp.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

AUG 21 1996
821-96

Jack L. Yinger (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Address) Jack L. Yinger - VP
P.O. Box 247, Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 20 day of August, 19 96

GLEND A G. NEWELL
Notary Public - State of Kansas
My Appl. Expires 7/2/97

My Commission Expires: 7/2/97 Glenda G. Newell Notary Public