

LEASE NAME OCHAMPAUGH A

WELL NUMBER #2

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 26 TWP. 8S RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 8/30/95

Plugging Completed 8/30/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR GRAHAM-MICHAELIS CORP.

ADDRESS P.O. Box 247, Wichita, KS 67202

PHONE# (316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ ? _____ (date)

by Bruce Bayse _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation LANSING Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	172'	none
				4-1/2"	3398'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set 8/30/95 Mixed 500% hulls, 200 sacks of 60/40 poz mix with 10% gel. Loaded casing. Shut in pressure 300%. Pumped 15 sacks down backside @ 400%. Shut in.

Name of Plugging Contractor Graham-Michaelis Corp. License No. 5134

Address P.O. Box 232, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GRAHAM-MICHAELIS CORP. **RECEIVED SEP 22 1995**

STATE OF KANSAS COUNTY OF SEDGWICK, ss. **CONSERVATION DIVISION 9-22-95**
Wichita, Kansas

Jack L. Yinger - Vice President


(Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack L. Yinger

(Address) Jack L. Yinger
P.O. Box 247, Wichita, KS

Subscribed and sworn to before me this 20 day of Sept., 19 95

Glenda G. Newell
Notary Public



My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM

July 2, 1997



J. B. Collins
 1007 Cody - Suite A
 Hays, KS 67601

WELL LOG

15-163-20939-00-00

Sec. 26 Twp. 8 Rng. 17

Farm Ochampaugh No. 2

Location NE SW NE

Total Depth 3400'

County Rooks

Comm. 7-11-79 Comp. 7-29-79

Elevation: 1994 K. B.

Contractor Dreiling Oil, Inc.
 Rt. #1
 Victoria, KS 67671

1991 D. F.

1989 G. B.

Casing Record
 172' - 8 5/8"
~~3,396'~~ - 4 1/2"
 3398

Cement Record
 135 sacks cement
 cemented w/150 sacks

Production:

Figures Indicate Bottom of Formations

0'	100'	Top Soil
100'	177'	Blue Shale
177'	470'	Shale
470'	968'	Shale & Sand
968'	1150'	Red Bed
1150'	1281'	Shale
1281'	1320'	Anhydrite
1320'	2428'	Shale
2428'	3153'	Shale & Lime
3153'	3229'	Lime
3229'	3328'	Shale & Lime
3328'	3400'	Lime
3400'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION

SEP 22 1995

CONSERVATION DIVISION
 Wichita, Kansas


9-22-95

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc.
 upon oath states that the above and foregoing is a true and correct
 copy from the Daily Drilling Report from the Ochampaugh #2.


 JOSEPH A. HESS

Subscribed and sworn to before me this 3rd day of August, 1979.


 Cecilia Basgall Notary Public

CECILIA BASGALL
 NOTARY PUBLIC
 Ellis County, Kansas

My appointment expires: November 17, 1980.