

15-163-20237-00-01

API NUMBER 15-163-20,237 ⁰⁰⁰¹

LEASE NAME Ochampaugh

WELL NUMBER "B" 1-26

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 8S RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed

Plugging Commenced 12-3-93

Plugging Completed 12-7-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham-Michaelis Corp.

ADDRESS P. O. Box 247, Wichita, KS 67201

PHONE# (316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil (OWWO)

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3469'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	201'	none
				4 1/2	3468 1/2	958'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Sanded bottom @ 3080' & 4 sks cement. Shot @ 2401 & 2009, did not come free. Shot @ 1713.
Spotted 35 sks w/100# hulls @ 1600. Shot @ 1501. Pipe parted @ 958. Spotted 4 gal, 25 sks cement w/200# hulls. Shot @ 913, pipe came loose. Pulled to 812, spotted 45 sks w/100# hulls.
Pulled to 600, spotted 20 sks. Pulled rest of pipe, filled hole w/25 sks cement. 60/40 10%
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corp.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator Michaelis Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 93

Irene Herzberg
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION
 DEC 22 1993
 12-22-93
 CONSERVATION DIVISION