

15-163-20905-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202


Rooks County. Sec. 26 Twp. 8 Rge. 17W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
C SE NW NW

Lease Owner Graham-Michaelis Corporation  
Lease Name Hrabe Well No. 4-26  
Office Address P. O. Box 247, Wichita, Kansas 67201  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed April 15 1979  
Application for plugging filed (verbally) April 15 1979  
Application for plugging approved (verbally) April 15 1979  
Plugging commenced April 15 1979  
Plugging completed April 15 1979  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3460'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T.D. 3460'  
Set 1st plug at 550' with 70 sacks  
2nd plug at 240' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 5 sacks  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 5:45 a.m., 4-15-79.

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

APR 27 1979

STATE OF Kansas COUNTY OF Sedgwick  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 79



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

15-163-20909-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Graham-Michaelis Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	HRABE #4-26
LOCATION:	C SE NW NW, Section 26-8-17W Rooks County, Kansas
SPUD DATE:	April 07, 1979
COMPLETION DATE:	April 15, 1979

0	158	Sand and shale
158	265	Sand
265	1300	Shale and sand
1300	1333	Anhydrite
1333	1407	Shale - Red beds
1407	1906	Shale and sand
1906	2907	Shale and lime
2907	3045	Lime and shale
3045	3200	Shale and lime
3200	3250	Lime
3250	3285	Shale and lime
3285	3460	Lime
	3460	Rotary Total Depth

Spud hole at 9:00 p.m., April 07, 1979. Drilled 265' of 12 1/4" hole. Ran 6 joints of new 24# - 8-5/8" casing. Set at 258.18' K.B. with 190 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 4:00 a.m., April 08, 1979.

T.D. 3460'. Set 1st plug at 550' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 5:45 a.m., April 15, 1979.

SAMPLE TOPS:

Anhydrite 1300'  
B/Anhydrite 1333'

427-79  
RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1979

STATE OF KANSAS     )  
                                  ) ss  
COUNTY OF SEDGWICK )


CONSERVATION DIVISION  
Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Hrabe #4-26, C SE NW NW, Section 26-8-17W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
Jack L. Partridge  
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 25th day of April, 1979.



Sherrie L. Brooks  
Sherrie Brooks, Notary Public

My commission expires 8-21-82.