

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19544-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 3-23S-4E
5091 feet from S Section Line, 5135 feet from E Section Line
Lease Name: VERVNYCK Well #: 1
County: BUTLER Total Vertical Depth: 2119 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	0		UNKNOWN
SURF	8.625	0		UNKNOWN

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: PARTIAL
Date/Time Plugging Completed: 09/18/2006 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

9/14/2006 -- Circulated hole clean at 2075'.
9/15/2006 -- Spotted tubing at 2050'. United Cementing mixed and pumped 25 sacks of 60/40 posmix with 4% gel. POOH with tubing at 250'. United Cementing mixed and pumped 119 sacks of 60/40 posmix with 4% gel (first 70 sacks were 2% CC) and circulated cement. Swedged into 5-1/2" casing and pumped 142 sacks of 60/40 posmix with 4% gel. Lost circulation. RIH with 1" at 250'. United Cementing pumped 14 sacks of 60/40 posmix with 4% gel.
300 sacks of 60/40 posmix with 4% gel
United Cement #7241
9/18/2006 -- RIH with 1" tubing on backside at 250'. United Cementing mixed and pumped 77 sacks of 60/40 posmix with 4% gel. RIH with 1" tubing on inside at 250'. United Cementing mixed and pumped 86 sacks of 60/40 posmix with 4% gel to surface.
60/40 posmix with 4% gel
United Cement #7243


RECEIVED
KCC DISTRICT #2
SEP 27 2006
WICHITA, KS

Remarks: CONTROL # 2006-0027-002

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS

