

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-19005-00-00
Spot: NESWSE Sec/Twnshp/Rge: 20-16S-1W
1004 feet from S Section Line, 1724 feet from E Section Line
Lease Name: VAN METER Well #: 2
County: SALINE Total Vertical Depth: 2631 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 403 FRONT STREET
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2625	0	160 SX
SURF	10	130	0	100 SX

\$ 85.51

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2006 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S. MEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-2312

Proposed Plugging Method: Run tubing to hole bottom and pump 35 sxs. Pull tubing to 300' and pump cmt to circ to surf.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2006 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Ran tubing to 2570' and pumped 35 sacks of cement to plug bottom. Pulled tubing to 300' and pumped 135 sacks of cement to circulate to surface. Production casing was previously perforated at 300'. Topped off with 23 sacks of cement on 9/28/2006.
60/40 posmix with 4% gel
Copeland #031209

Perfs:

RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS

INVOICED
DATE 1-4-07
INV. NO. 2007061057

Remarks:
Plugged through: TBG

District: 02

Signed Meg Eves
(TECHNICIAN)

M

RECEIVED
KANSAS CORPORATION COMMISSION 2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

PRET