

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-19006-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 20-16S-1W  
2323 feet from S Section Line, 2386 feet from E Section Line  
Lease Name: VAN METER Well #: 3  
County: SALINE Total Vertical Depth: 1908 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 403 FRONT STREET  
CLAFLIN, KS 67525

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 4.5   | 1908       | 0           | 50 SX   |
| SURF   | 8.625 | 208        | 0           | 100 SX  |

*\$62.01*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2006 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: EDWARDS S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-2312

Proposed Pumping Method: Pump 35 sxs above top perms; perf pipe at 300'; circ through tubing from 300' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/27/2006 12:00 PM KCC Agent: GREG EVES

**Actual Plugging Report:**

Ran tubing to 1900' and pumped 35 sacks of cement. Pulled tubing to 300' and pumped 90 sacks of cement to circulate to surface. Production casing was previously perforated at 300'. Topped off with 10 sacks of cement on 9/29/2006.

60/40 posmix with 4% gel

Copeland #031208

**Perfs:**

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 1857 | 1860 |      |          |

**RECEIVED  
KCC DISTRICT #2  
OCT 30 2006  
WICHITA, KS**

**INVOICED**  
DATE 1-4-07  
INV. NO. 2007061057

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)

**RECEIVED  
KANSAS CORPORATION COMMISSION-2/3  
DEC 29 2006  
CONSERVATION DIVISION  
WICHITA, KS**

*PKT*