

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22424-00-00
Spot: W2SENESE Sec/Twnshp/Rge: 23-32S-4W
1610 feet from S Section Line, 620 feet from E Section Line
Lease Name: WEISHAAR Well #: 6-G
County: SUMNER Total Vertical Depth: 4463 feet

Operator License No.: 32346
Op Name: BARTELSON, MITCHEL DBA BARTELS
Address: 118 N. ANSON RD.
MAYFIELD, KS 67103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2026		100 SX
SURF	8.625	253		200 SX

\$ 145.05

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/28/2006 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand 50' above perfs; cap w/ 5 sxs; recover casing; 35 sxs @ 650'; circ from 300' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/28/2006 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perforations at 2001' - 2005'. The perforations were covered with sand to 1930' and capped with 5 sacks of cement. The casing was recovered from 1225' and pulled to 650' where 35 sacks of cement were spotted. The casing was pulled to 300' where cement was circulated to surface.

60/40 posmix with 4% gel

Consolidated

Perfs:


Top	Bot	Thru	Comments
2001	2005		RECEIVED KCC DISTRICT #2 OCT 30 2006 WICHITA, KS

INVOICED
DATE 1-4-07
INV. NO. 2007061048

Remarks:

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

AKS