

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05473-00-01
Spot: SESWSW Sec/Twnshp/Rge: 13-19S-2W
308 feet from S Section Line, 4417 feet from E Section Line
Lease Name: LOVETT F A Well #: 5
County: MCPHERSON Total Vertical Depth: 3410 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2986		
PROD 7		3389		250 SX
SURF	13.38	219		200 SX

\$ 110.83

Well Type: EOR UIC Docket No: E09787.1 Date/Time to Plug: 09/28/2006 10:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P. BANDY Company: CYCLONE WELL SERVICE, INC. Phone: (620) 628-4428

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/28/2006 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Packer and tubing shot off at 2760'. Ran tubing to 2755' and pumped 35 sacks of cement. Perforated at 450' and set bridge just below. Ran tubing to 450' and circulated cement to surface.

60/40 posmix with 4% gel

United #7250 & #7251
Dyna Log, Inc. #944

Perfs:

Top	Bot	Thru	Comments
3389	3410		OPEN HOLE
2959	2972		

RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS

INVOICED
DATE 1-4-07
INV. NO. 2007061047

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION-2/3

DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS