

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-027-20035-00-00
Spot: NESW Sec/Twnshp/Rge: 3-9S-4E
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: WELLER Well #: 1
County: CLAY Total Vertical Depth: 1995 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1990	1250	100 SX CMT.
SURF	8.625	217	0	115 SX CMT.

64.84

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 50' above top perforations; cap with 5 sxs; circ w/ cement from 270' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: NONE
Date/Time Plugging Completed: 08/04/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded bottom to 1870' and capped with 5 sacks of cement. Pulled casing to 310' and circulated 118 sacks of cement from 310' to surface.

60/40 posmix with 4% gel

United #7075

Perfs:

Top	Bot	Thru	Comments
1939	1943		
1924	1927		
1920	1922		

RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS

INVOICED
DATE 1-4-07
INV. NO. 2007061047

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

m

PKT