

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22395-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 24-32S-4W
357 feet from S Section Line, 4808 feet from E Section Line
Lease Name: WEISHAAR Well #: 1-G
County: SUMNER Total Vertical Depth: 1482 feet

Operator License No.: 32346
Op Name: BARTELSON, MITCHEL DBA BARTELS
Address: 118 N. ANSON RD.
MAYFIELD, KS 67103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1476		125 SX.
SURF	8.625	250		175 SX. # 48.17

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/29/2006 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PBTD 1476'; OH 1476'-1482'; sand to 1426' and 4 sxs; 35 sxs @ 650'; circ 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/29/2006 11:33 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The open hole was filled with sand to 1380' and capped with 4 sacks of cement. The casing was recovered from 1015'. Pulled to 650' and pumped 35 sacks of cement. Casing was pulled to 300' and cement was circulated to surface.

60/40 posmix with 4% gel

Consolidated

Perfs:

Top	Bot	Thru	Comments
1476	1482		OPEN HOLE

**RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS**

INVOICED
DATE 1-4-07
INV. NO. 2007061048

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

**RECEIVED
KANSAS CORPORATION COMMISSION**
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

PKT